BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura division
B.B.M.P., Bangalore - 92
T.N.02/2010-11 Dated: 21-01-11

DRAFT TENDER SCHEDULE - B

Issued to :

Original / Duplicate
Item No. 105

Name of Work : Improvements of Drains and Store Water Drain in Ward No. 8 Kodigehalli Sub Division.

Sl. No.	Approved Quantity	Description	Unit	Sanctioned Rates	Rates Quoted by the Contractor	
				In Figures	In Figures	In Words
1	122.37	KSRB 300.2 : Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be leveled neatly	cum	77.76		
2	22.94	KSRRB 2900-4.1: Providing and laying in position plain cement concrete mix 1:4:8 with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Page 12 & Item No. 4.3)	cum	3349.08		
	458.88	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2. (Page No. 14 & Item No. 4.31)	Sqm	199.80		
	53.54	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6. (Page No. 12 & Item No. 4.11)	cum	4902.12		

Sl. No.	Approved Quantity	Description	Unit	Sanctioned Rates	Rates Quoted by the Contractor	
				In Figures	In Figures	In Words
	48.18	KSRB 4.9.2 : Providing T.M.T. Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (Page No. 16 & Item No. 4.46)	Qtl	5204.52		
	122.37	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	cum	67.32		

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಮುಖ್ಯಾಂಕ ಪಲಯ
ಬೆಂಗಳೂರು 560092